

BAKU – TBILISI – CEYHAN CRUDE OIL PIPELINE PROJECT REINSTATEMENT

- REINSTATEMENT OVERVIEW
- INTERACTIVE DIALOG

Prepared by


Hugo Blacud

Şükran Şahin

Mustafa Çelikel





Kaynak: Blacud vd, 2004. Eski Haline Getirme. BTC Ham Petrol Boru Hattı Çevre İzleme ve Yönetimi Eğitim Materyali. Çınar Müh. ve BOTAS, Adana.




REINSTATEMENT

BEFORE CONSTRUCTION




- GENERAL INFORMATION about flora, fauna, soil, topography. etc.
- ADDITIONAL INFORMATION in order to develop SARMS for Special Areas



- Topsoil assessment form
- Plant enumeration form


REINSTATEMENT

DURING CONSTRUCTION





TOPSOIL STRIPPING AND STOCKPILING

- 
- Strip to its full depth (typically 150-300 mm)
 - Stockpile not more than 2 meters high with side slopes $<45\%$,
 - Compact stockpile surface lightly to reduce rainfall penetration but not enough to promote anaerobic conditions,
 - Impliment suitable drainage and erosion control measures

**NEXT**

TOPSOIL STRIPPING AND STOCKPILING IN PARTICULAR AREAS

-  ■ Rocky areas
-  ■ Wetlands
-  ■ Snow conditions
-  ■ ESAs



BACK


SUBSOIL REMOVAL AND STORAGE

- Subsoil is excavated from both trenches and also from cut areas of side and steep slopes
- Subsoil storage areas at extra lands requires approved environmental assessment report including topsoil management and land owner permit



REINSTATEMENT

AFTER CONSTRUCTION





LANDSHAPING/RECONTOURING


- Shape the disturbed areas to conform as nearly as possible to the original land contour.
- Tie reconstructed area with the surrounding landscape providing smooth, continuous sequence of hill slopes and valley floors.



BACK




LAND AND SOIL REINSTATEMENT

- Subsoil from the trench excavation and from clearing & grading activities should be returned to their original locations as much as possible, and compacted to the similar condition to the adjacent undisturbed area.
-  Before spreading the topsoil over the compacted subsoil, the subsoil layer will be horrowed
- Topsoil would be redistributed over the entire disturbed area

LAND NATURALIZATION

Design and impliment a naturalization work where it is not possible turning back the topography to its original shape



Methods of naturalizing highwalls and rock cuts



BACK

PERMANENT EROSION CONTROL

Permanent erosion control measures stabilise and preserve soil against erosion before biore Restoration works start.



BACK


INTERVAL DITCH TERRACES

- This technique is very suitable for the plantation works in steep slopes (>12%)
- As this technique requires a small amount of soil excavation, it is a proper technique for the places where the soil depth is low.
- It is a cost effective technique providing large water retention capacity within the channel with a small amount of soil excavation.
- The surplus rocky material taken from RoW can be used as a retaining material for the terraces, supporting long term efficiency of the technique
- The ditches retain the water and give opportunity for water percolation and followingly lateral water flow within the soil supporting plant roots development at the intervals between the terraces as well as surface stabilization.
- In slopes where the soil depth is high, this technique can be implemented easily to avoid erosion.



NEXT

INTERVAL DITCH TERRACES



BACK




POCKET TERRACES

- This is a proper technique in steep slopes (>20%)
- The pocket terraces implementations are one of the proper techniques for the slopes where the soil depth is low, and the outcrop formations are present.
- The pocket terraces in crescent form retain water and soil, and support tree and shrub growth.
- The surplus rocky material taken from RoW can be used as a retaining material for the terraces supporting long term efficiency of the technique.
- The diameter of the pocket terraces is min 2m for the shrubs. For the trees the radius can be defined in accordance with the crown size of the trees. In proper areas the size of the pocket terraces can be increased to provide planting basin for more trees, and also for the more effective erosion control. This technique is called **intermittent stone bench**.

**NEXT**

POCKET TERRACES and INTERMITTENT STONE BENCHES

Pocket terraces



Intermittent stone benches



BACK

TERRACES TYPE CONTOUR FIGURATIONS OF STONES IN STEEP SLOPES

- This technique can be implemented at the slopes where the soil depth is low and slope gradient is more than 12%.
- The surplus rocky material taken from RoW can be used to implement this technique.
- The ditch line in contour at the terraces is connected to outlets giving 0.5-1% slope angle for the runoff water discharge




NEXT

TERRACES TYPE CONTOUR FIGURATIONS OF STONES IN STEEP SLOPES



1. SMALL SCALE ROCK STACK

A. WITOUT SOIL

A. WITH SOIL



2. MODERATE SCALE DRY ROCK WALL AND STACK



SMALL SCALE STACK

DRY WALL



BACK

BIORESTORATION

MAIN FOCUSES

- **Conserving the landscape and biodiversity**
- **Supporting erosion control measures**


WITHIN THE CONTEXT OF

- **ESAs Bio restoration**
- **General Bio restoration Strategy**



BACK

ECOLOGICALLY SENSITIVE AREAS- ESA 44



TARGET SPECIES AT EAS 44, ESA 47 AND ESA 46

Bilimsel adı

- *Verbascum luridiflorum*
- *Thlaspi cilicicum*
- *Cephalantera kotschyana*
- *Centaurea lycopifolia*
- *Fritillaria alfredae* Post. ssp. *Glaucoviridis*
- *Lamium garamicum* L. ssp. *nepetifolium*
- *Cyclamen pseudo-ibericum*

Türkçe adı

- : Sığırkuyruğu
- : Akça çiçeği
- : Sefelantera
- : Peygamber çiçeği
- : Terslale, ağlayan gelin
- : Ballıbaba
- : Siklamen



NEXT

TARGET SPECIES AT EAS 44, ESA 47 AND ESA 46



Centaurea lycopifolia Boiss. & Kotschy – ESA 47, 46



Cyclamen pseudo-ibericum
Hildebr. – ESA 46



Fritillaria alfredae Post. ssp.
Glaucoviridis – ESA 46



NEXT

TARGET SPECIES AT EAS 44, ESA 47 AND ESA 46



Lamium garganicum L.
ssp. *nepetifolium* (Boiss.)
R. Mill – ESA 46



Verbascum luridiflorum
Hub. - Mor. – ESA 44



Cephalanthera kotschyana
Renz&Taub. Hayek – ESA 44



Thlaspi cilicicum (Boiss.)
Hayek – ESA 44, ESA 46



NEXT

SARMS CHART FOR ESAs (ESA 44, ESA 46 and ESA 47)

KP LOCATION	SARMS TYPE	KP LOCATION OF AIP	DISTANCE (m)	BIORESTORATION STRATEGY			BIORESTORATION SCHEDULE
				Plant Scientific Name	Restoration	Monitoring	
955-910-961-010	ESA 44	AIP-44-A: 958+795-958+800	5	<i>Verbascum luridiflorum</i>	SC&S	Sprout check	2nd half of Nov.
				<i>Thlaspi cilicicum</i>	SC&S	Sprout check	2nd half of Nov.
		AIP-44-B: 959+752-959+790	38	<i>Cephalanthera kotschyana</i>	TSM	Sprout check	Reinstatement Chart
				<i>Thlaspi cilicicum</i>	SC&S		2nd half of Nov.
974-540-981-650	ESA 46	AIP-46-A: 977+210-977+550	340	<i>Centaurea lycopifolia</i>	TSM	Sprout check	Reinstatement Chart
				<i>Thlaspi cilicicum</i>	SC&S		Late Oct. or early Nov.
		AIP-46-B: 978+800-979+300	500	<i>Fritillaria alfredae</i> Post. ssp. <i>Glaucoviridis</i>	BC&R		2nd half of Oct.
				<i>Lamium garamicum</i> L. ssp. <i>nepetifolium</i>	SC&S		Late Oct. or early Nov.
				<i>Cyclamen pseudo-ibericum</i>	TSM		Reinstatement Chart
		AIP-46-C: 980+530-980+590	60	<i>Cyclamen pseudo-ibericum</i>	PR		Flowering check
994-290-994-740	ESA 47	AIP-47-A: 994+200-994+800	600	<i>Centaurea lycopifolia</i>	TSM	Sprout-check	Reinstatement Chart
1026-500-1028+500	ESA 48	AIP-48-A: 1028+100-1028+000	100	<i>Anthemis pungens</i> Yaviv	TSM	Sprout-check Re-seeding	Reinstatement Chart
		AIP-48-B: 1028+400-1028+390	10	<i>Tordylium pustulosum</i> Boiss	SC&S		2nd half of Nov.

TSM : Topsoil Management
 SC&S : Seed Collection and seeding
 SC&SI : Seed Collection and seedling
 BC&R : Bulb collection and replanting
 BC&SI : Bulb collection and seedling
 PR : Permanent relocation
 T : Translocation to the vicinity and re-plant-back






SURFACE MANIPULATION

- Prepare the surface of disturbed lands to receive seed and provide proper soil environment for tree planting .
- Leave the graded surface in a roughened condition to improve permeability and provide micro-sites for seed germination
- Most type of surface manipulation are standard agricultural techniques such as chiselling, disking, harrowing.

**NEXT**

SURFACE MANIPULATION



- A chisel and disk can break up a soil crust and incorporate fertilizer
- Both disking and chiselling are usually followed by horrowing to break up small clods and prepare a fine seedbed for drill seeding
- For the broadcast seeding, chiselling and disking may be the final seedbed activity, since a rougher seedbed is more desirable for broadcast seeding than drill seeding





SOIL AMENDMENTS

In according to soil structure and texture
improve soil physical and chemical conditions for vegetation growth.



BACK



REVEGETATION

Major issues for the successful tree seedling establishment


- selection of proper native species
- purchase of the best quality planting stock
- correct handling of planting stock
- correct planting techniques
- effective control of competing vegetation
- proper soil conditions and preparation
- weather



NEXT

REVEGETATION

REVEGETATION



NURSERIES

Main focuses



- Nursery conditions



- Plant characteristics

WASTE SURPLUS MATERIAL MANAGEMENT

Dispose surplus material in accordance with the requirements of the Waste Management Plan



BACK

REINSTATEMENT MARCH CHART



BACK



POST-REINSTATEMENT ACTIVITIES



BACK



PRE-CLEARANCE SURVEY & DATA COLLECTION



PUNJ LLOYD LIMAK JV
BAKU - TBILISI - CEYHAN
CRUDE OIL PIPELINE PROJECT LOT - C



TOPSOIL ASSESSMENT FORM

Name of the Evaluator :

Date :

Equipment used/ Assessment Methodology :

Sampling/ Assessment location	Representing chainage		Top Soil Depth	Nature of Topsoil/ Color/ Remarks
	From	To		



BACK



PRE-CLEARANCE SURVEY & DATA COLLECTION



PUNJ LLOYD LIMAK JV
BAKU - TBILISI - CEYHAN
CRUDE OIL PIPELINE PROJECT LOT - C

TREE ENUMERATION FORM

Name of the Enumerator :

Date :



<u>Chainage</u>		Trees	Total	Shrubs	Density
From	To				



BACK



***TOPSOIL REMOVAL &
STORAGE***



NEXT

TOPSOIL REMOVAL & STORAGE



BACK

TOPSOIL REMOVAL & STORAGE
Rocky areas



NEXT

TOPSOIL REMOVAL & STORAGE
Rocky areas



BACK

TOPSOIL REMOVAL & STORAGE Wetlands



Working over trackmat without topsoil/turf stripping



NEXT

TOPSOIL REMOVAL & STORAGE Wetlands



NEXT

TOPSOIL REMOVAL & STORAGE Wetlands



BACK

TOPSOIL REMOVAL & STORAGE ***Snow conditions***



BACK

TOPSOIL REMOVAL & STORAGE ESAs



NEXT

TOPSOIL REMOVAL & STORAGE ESAs



NEXT

TOPSOIL REMOVAL & STORAGE ESAs



NEXT

TOPSOIL REMOVAL & STORAGE ESAs



NEXT

TOPSOIL REMOVAL & STORAGE ESAs



BACK

SUBSOIL REMOVAL & STORAGE



BACK

TEMPORARY EROSION CONTROL MEASURES ***Silt fences***



Structures installed at low sheet flow areas to intercept runoff



NEXT

TEMPORARY EROSION CONTROL MEASURES

Silt fences



BACK

TEMPORARY EROSION CONTROL MEASURES ***Diversion and discharge channel***



Diversion Channels: Structures installed transverse to RoW to divert water flow coming from upper watershed

Discharge Channels Structures installed longitudinal to RoW to connect slope breakers safely with the outlets



BACK

TEMPORARY EROSION CONTROL MEASURES

Wooden fences




Structures installed at side slopes and ridge constructions to avoid landslides and soil losses



BACK

TEMPORARY EROSION CONTROL MEASURES

Outlets



BACK

TEMPORARY EROSION CONTROL MEASURES ***Slope breaker***



Graded channels across RoW width at the steep slope to remove surface runoff and mitigate erosion



BACK

TEMPORARY EROSION CONTROL MEASURES ***Ditch/trench breakers***



Structures installed in the open trench and removed before lowering the pipe to arrest flows inside the trench



BACK

TEMPORARY EROSION CONTROL MEASURES ***Water disposal***




Activities to discharge turbid and sediment laden water accumulated in trench, and to discharge hydrotest water using proper filtering structures



BACK

TEMPORARY EROSION CONTROL MEASURES

Straw bales



Structures installed in areas where small amounts of temporary sediment interception are required



NEXT

TEMPORARY EROSION CONTROL MEASURES
Straw bale barriers



LANDSHAPING / RECONTOURING
Land and Soil Reinstatement



NEXT

***LANDSHAPING / RECONTOURING
Land and Soil Reinstatement***



NEXT

***LANDSHAPING / RECONTOURING
Land and Soil Reinstatement***




BACK

PERMANENT EROSION CONTROL MEASURES ***Jute Matting***



NEXT

PERMANENT EROSION CONTROL MEASURES
Jute Matting



BACK

PERMANENT EROSION CONTROL MEASURES ***Jute Matting***



PERMANENT EROSION CONTROL MEASURES
Gabions



PERMANENT EROSION CONTROL MEASURES
Slope breakers



NEXT

PERMANENT EROSION CONTROL MEASURES
Slope breakers



NEXT

PERMANENT EROSION CONTROL MEASURES
Slope breakers



***PERMANENT EROSION CONTROL MEASURES
RipRap&Crashed Rock***



BACK

PERMANENT EROSION CONTROL MEASURES
Outlet structures



NEXT

PERMANENT EROSION CONTROL MEASURES
Outlet structures



PERMANENT EROSION CONTROL MEASURES
Diversion channel



PERMANENT EROSION CONTROL MEASURES
Discharge channel



PERMANENT EROSION CONTROL MEASURES ***Gully remediation***



BACK


PERMANENT EROSION CONTROL MEASURES ***Ditch breaker and drainage***




PERMANENT EROSION CONTROL MEASURES
Terraces Type Contour Figurations of Stones in Steep Slopes




BIO-RESTORATION Surface Manipulation



BIO-RESTORATION Ripping



BIO-RESTORATION Surface Manipulation




Methods of roughening slopes to slow runoff



NEXT

BIO-RESTORATION **Surface Manipulation**



Surface-roughening methods of concentrating precipitation



BACK

BIO-RESTORATION **Plant selection**

The plants for restoration should be selected from native vegetation cover.



For the plants which are not available might be compensated with the pioneering plants that can be defined from existing disturbed areas around.




BACK

ÇINAR




BIO-RESTORATION Nursery Conditions



BACK

BIO-RESTORATION

Plant material characteristics





Methods of containering reclamation plants



BACK

BIO-RESTORATION

Seed collection and plant translocation



NEXT

BIO-RESTORATION

Seed collection and plant translocation



Bulb collection




Plant translocation



BACK

BIO-RESTORATION

Seeding methods and applications



BIO-RESTORATION
Broadcast seeding



NEXT

BIO-RESTORATION
Hydroseeding, Broadcast seeding



NEXT

BIO-RESTORATION ***Tree and shrub planting***





Seeding at Ecologically Sensitive Areas




BACK

BIO-RESTORATION


Tree and shrub planting



BIO-RESTORATION Tree and shrub planting



Correct slope planting



Planting at locations with impervious soil condition




NEXT

BIO-RESTORATION **Tree and shrub planting**



Wrong plantation



NEXT

ÇINAR



BIO-RESTORATION
Tree and shrub planting



NEXT

ÇINAR

BIO-RESTORATION

Re-vegetation for special areas, riparian vegetation



BACK

ÇINAR

BIO-RESTORATION Aftercare Monitoring



Goat grazing pine, Horsell



NEXT

BIO-RESTORATION Fencing



BACK

ÇINAR



NEXT

ÇINAR



NEXT

ÇINAR



NEXT



NEXT

ÇINAR



NEXT

ÇINAR



NEXT

ÇINAR



NEXT

ÇINAR



NEXT

ÇINAR



NEXT

ÇINAR



NEXT

ÇINAR



NEXT

ÇINAR



NEXT

TOPSOIL REMOVAL & STORAGE



NEXT

ÇINAR



NEXT

ÇINAR



NEXT

ÇINAR



BACK






STANDART DRAWINGS

- [Sand bags](#)
- [Slope breakers](#)
- [Vegetated waterway and lined chute](#)
- [Outlet of slope breakers](#)
- [Sediment filter/trench water disposal](#)
- [Subsoil retaining wooden fences](#)
- [Silt fences and straw bale barrier](#)
- [Erosion control mating installation](#)
- [Concrete wall](#)



BACK

SAND BAGS



TYPICAL DISTANCE BETWEEN DITCH BREAKERS (m) TO BE ADAPTED TO SITE CONDITIONS		
INCLINATION OF BOTTOM OF TRENCH %	SAND AND GRAVEL (SOIL TYPE 1,2,3,4)*	CLAY AND SILT (SOIL TYPE 5,6,7)*
< 30%	IN CERTAIN CASES, 50 - 35	IN CERTAIN CASES, 45 - 30
30% - 60%	50 - 35	45 - 30
60% - 80%	35 - 25	30 - 20
80% - 100%	25 - 20 (NOTE 2)	20 - 15 (NOTE 2)
> 100%	15-20 (NOTE 2)	10-15 (NOTE 2)


- NOTES :**
- DRAINAGE : 2 x DN 100 mm (MIN.), L = 4.0 m. ALTERNATIVELY, GEOTEXTILE WRAPPED LOCAL GRAVEL MAY BE EMPLOYED.
 - ADDITIONAL TRENCH AND SLOPE PROTECTION TO BE EXECUTED AS REQUIRED BY SITE CONDITIONS.
 - D = PIPE DIAMETER.
 - IF INCLINATION OF BOTTOM OF TRENCH IS HIGHER THAN 50%, SAND-CEMENT-BAGS (SAND/CEMENT RATIO 10:1) ARE TO BE USED INSTEAD OF SAND-BAGS.
 - GENERALLY 4.0 m LENGTH SECTIONS THROUGH THE DITCH BREAKER, WHERE REQUIRED, OUTLETS ARE SHOWN IN ALIGNMENT SHEETS OR CAN BE LOCATED ON SITE IN CONJUNCTION WITH THE ENVIRONMENTAL INSPECTOR.
 - ALL DIMENSIONS IN METRES.

APPROVED FOR CONSTRUCTION	
BAKU - TBILISI - CEYHAN CRUDE OIL PIPELINE PROJECT	
MEP Participants	
BOTAS Petroleum Pipeline Corporation	
PROTECTION AGAINST EROSION WITH SAND-BAGS / SAND-CEMENT-BAGS	
ILF	DRG EPL PLG 835
temelsu	

SLOPE BREAKERS


TYPE I

SLOPE BREAKERS ON SINGLE SIDE



TYPE II

SLOPE BREAKERS ON BOTH SIDES



NOTES:

1. TYPE OF SLOPE BREAKERS ACCORDING TO TYPICAL DRAWING "CROSS SECTION OF SLOPE BREAKERS", SEC ILF-DRG-EPL-PLG-857.
2. FOR TYPE OF OUTLET SEE TYPICAL DRAWING "OUTLET OF SLOPE BREAKERS", ILF-DRG-EPL-PLG-858.
3. SPACING GIVEN IN ALIGNMENT SHEETS MAY BE CHANGED ACCORDING SITE SPECIFIC REQUIREMENT DEFINED FROM ENVIRONMENTAL INSPECTOR.
4. AREAS OF HIGHEST HISTORICAL RAINFALL AND SPECIAL AREAS SEE EIA REINSTATEMENT PLAN /SECTION 21.
5. AREAS OF LOWEST ANTICIPATED ROUTE RAINFALL.
6. ALL DIMENSIONS IN METRES.

SLOPE BREAKER SPACING CHART									
Kp 0 - 300 & Kp 900 - CEYHAN				Kp 300 - 900					
R I (NOTE 4)	SLOPE %	CLASS 1-2*	CLASS 3-5*	CLASS 6-7*	R II (NOTE 5)	SLOPE %	CLASS 1-2*	CLASS 3-5*	CLASS 6-7*
	0 - 14	100	80	60		0 - 14	120	100	80
	15 - 32	80	60	40		15 - 32	100	80	60
	33 - 40	60	40	20		33 - 40	80	60	40
	> 40	40	20	10		> 40	60	40	20





* REFER TO EIA REINSTATEMENT PLAN - SECTION 10

0		APPROVED FOR CONSTRUCTION		[Signatures]	
BAKU - TBILISI - CEYHAN CRUDE OIL PIPELINE PROJECT					
MEP Participants					
BOTAS Petroleum Pipelines Corporation					
SLOPE BREAKERS					
[temelsu Logo]		ILF DRG EPL PLG 855		Rev. Sum	
YOKSEL PROJE		0		0	



NEXT

CROSS SECTION OF SLOPE BREAKERS



STYLE SELECTION GUIDE

SLOPE %	CLASS 1-2*	CLASS 3-5*	CLASS 6-7*
0 - 14	A	B	B
15 - 32	A	B	C
33 - 40	B	B	C
> 40	B	C	C

* REFER TO SECTION 10 - EIA REINSTATEMENT PLAN

NOTES:


- LAYOUT OF SLOPE BREAKERS TO BE APPLIED ACCORDING TO TYPICAL DRAWING ILF-DRG-EPL-PLG-855.
- TYPE OF CROSS SECTION AS PER ALIGNMENT SHEETS OR AS REQUIRED AND DEFINED ON SITE FROM ENVIRONMENTAL INSPECTOR.
- SUBSTITUTED IN AREAS OF ROCK FOR TYPE A, B OR C.
- ALL DIMENSIONS IN METRES.

APPROVED FOR CONSTRUCTION			
BAKU - TBILISI - CEYHAN CRUDE OIL PIPELINE PROJECT			
MEP Participants			
CROSS SECTION OF SLOPE BREAKERS			
ILF DRG EPL PLG 857			




BACK

VEGETATED WATERWAY AND LINED CHUTE




TYPE I / W
VEGETATED WATERWAY





CROSS-SECTION A - A

TYPE II / W
LINED CHUTE



CROSS-SECTION A - A

TYPE III / W
LINED CHUTE



NOTES:

1. VEGETATED WATERWAY TO BE USED FOR CONTROLLED RUN OFF FROM SPRINGS OR WET AREAS ON SLOPES MAX. 10%.
2. LINED CHUTES TO BE USED FOR CONTROLLED RUN OFF FROM SPRINGS OR WET AREAS ON SLOPES STEEPER 10% OR FROM GULLIES.
3. OUTLET OF VEGETATED WATERWAY / LINED CHUTES TO BE ESTABLISHED IN SECURE, NON ERODIBLE AREAS.
4. ALL DIMENSIONS IN METRES.


APPROVED FOR CONSTRUCTION		[Signatures]	
BAKU - TBILISI - CEYHAN CRUDE OIL PIPELINE PROJECT			
MEP Participants			
BOTAS Petroleum Pipeline Corporation			
VEGETATED WATERWAY / LINED CHUTE			
temelsu		ILF DRG EPL PLG 858	
YOKBEL PROJE		0	




BACK

OUTLET OF SLOPE BREAKERS

TYPE I
RE-VEGETATED OUTLET
(NOTE 4)



TYPE II
STONE FILLED OUTLET
(NOTE 4)



NOTES:


1. IF OUTLET OF SLOPE BREAKERS IS NOT IN WELL VEGETATED AREA, STABILISATION BY VEGETATION OR ROCKS OR STAKED STRAW BALES / SILT FENCE IS REQUIRED.
2. LAYOUT AND CROSS SECTION OF SLOPE BREAKERS ACCORDING TO: ILF-DRG-EPL-PLG-855, ILF-DRG-EPL-PLG-857.
3. TYPE OF OUTLET AS PER ALIGNMENT SHEETS OR AS REQUIRED AND DEFINED ON SITE FROM ENVIRONMENTAL INSPECTOR.
4. IN THE EVENT THAT AREA IS UNSUITABLE TO ACCEPT RUN-OFF USE WATERWAY/CHUTE DRAWING ILF-DRG-EPL-PLG-858
5. ALL DIMENSIONS IN METRES.

NO.	DATE	DESCRIPTION	BY	CHECKED	APPROVED
1	14.08.2002	APPROVED FOR CONSTRUCTION			
BAKU - TBILISI - CEYHAN CRUDE OIL PIPELINE PROJECT					
MEP Participants					
BOTAS Petroleum Pipeline Corporation					
ILF OUTLET OF SLOPE BREAKERS					
temelsu ILF DRG EPL PLG 856					



BACK


SEDIMENT FILTER/TRENCH WATER DISPOSAL




BACK

SUBSOIL RETAINING WOODEN FENCES


WOODEN FENCE ON SLOPE $\leq 30^\circ$




WOODEN FENCE ON SLOPE $> 30^\circ$



WOODEN FENCE ON NARROW RIDGE
(METALLIC POST)



REINFORCED WOODEN FENCE
ON SLOPE $> 30^\circ$



NOTES:


1. CONTRACTOR TO ENSURE FENCE DESIGNS ARE SUITABLE FOR LOADS IMPOSED.
2. FENCES TO BE REMOVED PRIOR TO FINAL REINSTATEMENT UNLESS DIRECTED OTHERWISE BY EMPLOYER REPRESENTATIVE.
3. CONTRACTOR MAY PROPOSE ALTERNATIVE DESIGNS. THESE SHALL BE SUBJECT TO WRITTEN APPROVAL BY EMPLOYER.
4. LOCATION OF WOODEN FENCES TO BE DETERMINED BY CONTRACTOR AND AGREED WITH COMPANY ON SITE.
5. REFERENCE SHALL BE MADE TO THE PROJECT REINSTATEMENT SPECIFICATION.
6. ALL DIMENSIONS IN MILLIMETRES.

APPROVED FOR CONSTRUCTION			
BAKU - TBILISI - CEYHAN CRUDE OIL PIPELINE PROJECT			
MEP Participants			
BOTAS Petroleum Pipelines Corporation			
TEMELSU Subsoil Retaining Structures			
SUBSOIL RETAINING WOODEN FENCES		ILF DRG EPL PLG 862	




BACK

SILT FENCE AND STRAW BALE BARRIER




CROSS SECTION



NOTES:


1. SILT FENCES SHALL BE INSTALLED IN AREAS WHERE SHEET FLOW OR RELATIVELY SMALL VOLUMES OF WATER CAN BE EXPECTED TO OCCUR.
2. THE FILTER FABRIC SHALL BE ANCHORED IN A 0.15 m x 0.15 m TRENCH WITH WELL COMPACTED BACKFILL OVER THE FABRIC TO PREVENT PIPING.
3. SILT FENCES AND STRAW BALE BARRIER SHALL BE CHECKED AND MAINTAINED ON A REGULAR BASIS. REMOVE ANY BUILD-UP OF SEDIMENT.
4. REFERENCE SHALL BE MADE TO THE EIA REINSTATEMENT PLAN.
5. WHERE ANCHORING CONDITIONS FOR THE SILT FENCE ARE POOR, STRAW BALES SHALL BE PLACED ON THE DOWNSTREAM SIDE OF THE FENCE.
6. WIDTH AS REQUIRED FOR ROW, SIDE SLOPE OR SLOPE BREAKER OUTLET.
7. INSTALL BALES LENGTHWISE ON THE CONTOUR, WITH ENDS OF ADJACENT BALES TIGHTLY ABUTTING ONE ANOTHER.
8. BOTH ENDS OF THE BARRIER SHALL BE TURNED AND EXTENDED UPSLOPE.
9. EACH BALE SHALL BE SECURED BY AT LEAST 2 STAKES. THE FIRST STAKE IN EACH BALE SHALL BE DRIVEN TOWARD THE PREVIOUSLY LAID BALE TO FORCE THE BALES TOGETHER.
10. EXCAVATED SOIL SHALL BE COMPACTED AGAINST THE UPHILL SIDE OF THE STRAW BALE BARRIER TO PREVENT PIPING.
11. ALL DIMENSIONS IN METRES.

CROSS SECTION



STRAW BALE BARRIER

(NOTE 6)




0 14 00 2002		APPROVED FOR CONSTRUCTION		
BAKU - TBILISI - CEYHAN CRUDE OIL PIPELINE PROJECT				
MEP Participants				
		SILT FENCE & STRAW BALE BARRIER		
		ILF DRG EPL PLG 861		
Dr	Des	Draw	Spec	Doc



BACK

EROSION CONTROL MATING INSTALLATION



NOTES:



1. INSTALL MATTING IN ACCORDANCE WITH THE PROJECT REINSTATEMENT SPECIFICATION AND THE MANUFACTURER'S INSTRUCTIONS.
2. PREPARE SOIL BEFORE INSTALLING BLANKETS INCLUDING GRADING, REMOVAL OF LARGE ROCKS AND DEBRIS.
3. EROSION CONTROL BLANKETS SHALL EXTEND COMPLETELY ACROSS DISTRIBUTED AREAS TO PROTECT ERODIBLE SURFACES.
4. BEGIN 1.0 m PAST THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN A MINIMUM 50 mm WIDE AND 150 mm DEEP TRENCH, BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.
5. ROLL THE BLANKETS DOWN THE SLOPE IN THE DIRECTION OF THE WATER FLOW.
6. AS AN ALTERNATIVE TO STAPLES, WOODEN STAKES MAY BE USED.
7. ENSURE COMPLETE CONTACT BETWEEN THE BLANKETS AND THE SLOPE FACE. ADDITIONAL STAPLES CAN BE USED TO ELIMINATE GAPS.

APPROVED FOR CONSTRUCTION			
BAKU - TBILISI - CEYHAN CRUDE OIL PIPELINE PROJECT			
MEP Participants			
BOTAS Petroleum Pipeline Corporation			
		EROSION CONTROL MATTING INSTALLATION	
		ILF DRG EPL PLO 363	



BACK

CONCRETE WALL



TYPICAL DISTANCE BETWEEN CONCRETE WALLS (m) TO BE ADAPTED TO SITE CONDITIONS

INCLINATION OF BOTTOM OF TRENCH %	SAND AND GRAVEL	CLAY AND SILT
80% - 100%	30 - 25 (NOTE 2)	25 - 20 (NOTE 2)
> 100%	20 - 25 (NOTE 2)	15 - 20 (NOTE 2)

NOTES :

1. DRAINAGE : 2 x DN 100 mm (MIN.), L = 4.0 m. ALTERNATIVELY, GEOTEXTILE WRAPPED LOCAL GRAVEL MAY BE EMPLOYED.
2. ADDITIONAL TRENCH AND SLOPE PROTECTION TO BE EXECUTED AS REQUIRED BY SITE CONDITIONS.
3. D = PIPE DIAMETER.
4. CONCRETE ACCORDING TO SPECIFICATION, SEE ILF-SPC-ESC-GEN-024.
5. GENERALLY 4.0 m LENGTH SECTIONS THROUGH THE DITCH BREAKER, WHERE REQUIRED. OUTLETS ARE SHOWN IN ALIGNMENT SHEETS & CAN BE LOCATED ON SITE IN CONJUNCTION WITH THE ENVIRONMENTAL INSPECTOR.
6. ALL DIMENSIONS IN METRES.

APPROVED FOR CONSTRUCTION		Date: 14.05.2008	
BAKU - TBILISI - CEYHAN CRUDE OIL PIPELINE PROJECT			
MEP Participants			
BOTAŞ Petroleum Pipeline Corporation		ILF	
PROTECTION AGAINST EROSION WITH CONCRETE WALL		Scale: 1:100	
temelsu	ILF	DRG	EPL
Scale: 1:100	Scale: 1:100	Scale: 1:100	Scale: 1:100
Sheet No: 0	Rev: 0	Rev: 0	Rev: 0



BACK